SECTION 064023 - INTERIOR ARCHITECTURAL WOODWORK

ALL LIBRARIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes the following:

1. Interior standing and running trim.
2. Interior ornamental work.
3. Built-In display cases
4. Plastic-laminate cabinets.
5. Plastic-laminate countertops.
6. Solid-surfacing-material countertops.
7. Built-In benches with seat cushions.
8. Closet and utility shelving.
9. Manufactured Pencil Drawer

B. Related Sections include the following:

1. Division 06 Section "Rough Carpentry" for wood furring, blocking, shims, and hanging strips required for installing woodwork and concealed within other construction before woodwork installation.

1.3 DEFINITIONS

A. Interior architectural woodwork includes wood furring, blocking, shims, and hanging strips for installing woodwork items unless concealed within other construction before woodwork installation.

1.4 ACTION SUBMITTALS

A. Product Data: For high-pressure decorative laminate, adhesive for bonding plastic laminate, solid-surfacing material, cabinet hardware, and accessories and finishing materials and processes.

1. Include data for fire-retardant treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements.

B. Shop Drawings: Show location of each item, dimensioned plans and elevations, large-scale details, attachment devices, and other components.

1. Show details full size.
2. Show locations and sizes of furring, blocking, and hanging strips, including concealed blocking and reinforcement specified in other Sections.
3. Show locations and sizes of cutouts and holes for plumbing fixtures, faucets, soap dispensers, and other items installed in architectural woodwork.
4. Show veneer leaves with dimensions, grain direction, exposed face, and identification numbers indicating the flitch and sequence within the flitch for each leaf.

C. Samples for Verification:

1. Lumber with or for transparent finish, not less than 5 inches (125 mm) wide by 24 inches (600 mm) long, for each species and cut, finished on 1 side and 1 edge.
2. Plastic laminates, 8 by 10 inches (200 by 250 mm), for each type, color, pattern, and surface finish, with 1 sample applied to core material and specified edge material applied to 1 edge.
3. Solid-surfacing materials, 6 inches (150 mm) square.
4. Exposed cabinet hardware and accessories, one unit for each type and finish.

1.5 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer and fabricator.

B. Product Certificates: For each type of product, signed by product manufacturer.

C. Woodwork Quality Standard Compliance Certificates: AWI Quality Certification Program certificates.

1.6 QUALITY ASSURANCE

A. Fabricator Qualifications: Shop that employs skilled workers who custom-fabricate products similar to those required for this Project and whose products have a record of successful in-service performance. Shop is a certified participant in AWI's Quality Certification Program.

B. Installer Qualifications: Certified participant in AWI's Quality Certification Program.

C. Source Limitations: Engage a qualified woodworking firm to assume undivided responsibility for production of interior architectural woodwork with sequence-matched wood veneers.

D. Quality Standard: Unless otherwise indicated, comply with AWI's "Architectural Woodwork Quality Standards" for grades of interior architectural woodwork indicated for construction, finishes, installation, and other requirements.

1. Provide AWI Quality Certification Program certificates indicating that woodwork, including installation, complies with requirements of grades specified.

E. Fire-Test-Response Characteristics: Where fire-retardant materials or products are indicated, provide materials and products with specified fire-test-response characteristics as determined by testing identical products per test method indicated by UL, ITS, or another testing and inspecting agency acceptable to authorities having jurisdiction. Identify with appropriate markings of applicable testing and inspecting agency in the form of separable paper label or, where required by authorities having jurisdiction, imprint on surfaces of materials that will be concealed from view after installation.

F. Mockups: Build mockups to verify selections made under sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Do not deliver woodwork until painting and similar operations that could damage woodwork have been completed in installation areas. If woodwork must be stored in other than installation areas, store only in areas where environmental conditions comply with requirements specified in "Project Conditions" Article.

1.8 PROJECT CONDITIONS

A. Environmental Limitations: Do not deliver or install woodwork until building is enclosed, wet work is complete, and HVAC system is operating and maintaining temperature and relative humidity at occupancy levels during the remainder of the construction period.

B. Field Measurements: Where woodwork is indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication, and indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

1. Locate concealed framing, blocking, and reinforcements that support woodwork by field measurements before being enclosed, and indicate measurements on Shop Drawings.
2. Established Dimensions: Where field measurements cannot be made without delaying the Work, establish dimensions and proceed with fabricating woodwork without field measurements. Provide allowance for trimming at site, and coordinate construction to ensure that actual dimensions correspond to established dimensions.

1.9 COORDINATION

A. Coordinate sizes and locations of framing, blocking, furring, reinforcements, and other related units of Work specified in other Sections to ensure that interior architectural woodwork can be supported and installed as indicated.

PART 2 - PRODUCTS

2.1 MATERIALS

A. General: Provide materials that comply with requirements of AWI's quality standard for each type of woodwork and quality grade specified, unless otherwise indicated.

B. Wood Species and Cut for Transparent Finish: White maple, plain sliced.

C. Wood Products: Comply with the following:

1. Hardboard: AHA A135.4.
2. Medium-Density Fiberboard: ANSI A208.2, Grade MD, made with binder containing no urea formaldehyde.
3. Particleboard: ANSI A208.1, Grade M-2, made with binder containing no urea formaldehyde.
4. Softwood Plywood: DOC PS 1, Medium Density Overlay.
5. Veneer-Faced Panel Products (Hardwood Plywood): HPVA HP-1, made with adhesive containing no urea formaldehyde.

D. Thermoset Decorative Panels: Particleboard or medium-density fiberboard finished with thermally fused, melamine-impregnated decorative paper complying with LMA SAT-1.

E. High-Pressure Decorative Laminate: NEMA LD 3, grades as indicated or, if not indicated, as required by woodwork quality standard.

1. Manufacturer: Subject to compliance with requirements, provide high-pressure decorative laminates by one of the following:

a. Formica Corporation.
b. Lamin-Art, Inc.

2. Basis of Design: PL-1, Vertical applications.

a. Manufacturer: Formica Corporation.
b. Color: Sorrel Cherry 5886-43.
c. Finish: Artisan.

3. Basis of Design: PL-2, Vertical applications.

a. Manufacturer: Lamin-Art, Inc.
b. Color: 3057-VT.
c. Finish: Velva-Tex.

4. Basis of Design: PL-3, Horizontal applications (Tops).

a. Manufacturer: Formica Corporation.
b. Color: Fog 961-58
c. Finish: Matte.

5. Basis of Design: PL-4, Vertical applications.

    a. Manufacturer: Formica Corporation.
    b. Color: Brushed Stainless Steel M2178.

6. Basis of Design: PL-5, Vertical and horizontal applications.

    a. Manufacturer: Formica Corporation.
    b. Color: Stop Red 839-58.
    c. Finish: Infiniti Finish.

7. Basis of Design: PL-6, Vertical and horizontal applications.

    a. Manufacturer: Formica Corporation.
    b. Color: Vibrant Green 6901-58.
    c. Finish: Infiniti Finish.

8. Basis of Design: PL-7, Vertical applications.

    a. Manufacturer: Formica Corporation.
    b. Color: Spectrum Blue 851-AN.
    c. Finish: Infiniti Finish.

F. Solid-Surfacing Material: Homogeneous solid sheets of filled plastic resin complying with ISSFA-2.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

    a. Avonite, Inc.

2. Type: Standard type, unless Special Purpose type is indicated.
3. Colors and Patterns: Nordic F1-9119.
4. Thickness: ¾ inches thick.

G. Fabric Material: Fabric from same dye lot; color and pattern as indicated on Drawings.

1. Basis of Design: FB-1A, Children’s Cushion.

    a. Manufacturer: Arc-Com.
    b. Product Line/Pattern: Axis.
    c. Style Number: AC-61346.
    d. Color: Chilli #7.
    e. Fiber Content: 100 percent vinyl face, 100% polyester back.
    f. Width: 54 inches (1371 mm).
    g. Applied Treatments: Stain resistance.

2. Basis of Design: FB-1B, Children’s Cushion.

    a. Manufacturer: Arc-Com.
    b. Product Line/Pattern: Axis.

c. Style Number: AC-61345.
d. Color: Pumpkin #6.
e. Fiber Content: 100 percent vinyl face, 100% polyester back.
f. Width: 54 inches (1371 mm).
g. Applied Treatments: Stain resistance.

3. Basis of Design: FB-1C, Children's Cushion.

a. Manufacturer: Arc-Com.
b. Product Line/Pattern: Axis.
c. Style Number: AC-61349.
d. Color: Lime #10.
e. Fiber Content: 100 percent vinyl face, 100% polyester back.
f. Width: 54 inches (1371 mm).
g. Applied Treatments: Stain resistance.

4. Basis of Design: FB-1D, Children's Cushion.

a. Manufacturer: Arc-Com.
b. Product Line/Pattern: Axis.
c. Style Number: AC-61340.
d. Color: Seaglass #1.
e. Fiber Content: 100 percent vinyl face, 100% polyester back.
f. Width: 54 inches (1371 mm).
g. Applied Treatments: Stain resistance.

5. Basis of Design: FB-1E, Children's Cushion.

a. Manufacturer: Arc-Com.
b. Product Line/Pattern: Axis.
c. Style Number: AC-61352.
d. Color: Ocean #13.
e. Fiber Content: 100 percent vinyl face, 100% polyester back.
f. Width: 54 inches (1371 mm).
g. Applied Treatments: Stain resistance.

H. Seat Cushions:

1. Seat cushions are constructed with a 2-inch – 1.8 pound density, 36 lb. polyurethane core wrapped with a 1-1/4 oz. Dacron with ticking.
2. All "Bio-Flex" – (Earth Friendly) polyurethane filling materials are treated with flame retardant agents to meet Cal Technical Bulletin 117.
3. Periodic reversing of cushions will insure uniform and even wear.

2.2 FIRE-RETARDANT-TREATED MATERIALS

A. General: Where fire-retardant-treated materials are indicated, use materials complying with requirements in this Article, that are acceptable to authorities having jurisdiction, and with fire-test-response characteristics specified.

1. Do not use treated materials that do not comply with requirements of referenced woodworking standard or that are warped, discolored, or otherwise defective.
2. Use fire-retardant-treatment formulations that do not bleed through or otherwise adversely affect finishes. Do not use colorants to distinguish treated materials from untreated materials.
3. Identify fire-retardant-treated materials with appropriate classification marking of UL, U.S. Testing, Timber Products Inspection, or another testing and inspecting agency acceptable to authorities having jurisdiction.

B. Fire-Retardant-Treated Lumber and Plywood by Pressure Process: Comply with performance requirements of AWPA C20 (lumber) and AWPA C27 (plywood).

C. Fire-Retardant Particleboard: Panels complying with the following requirements, made from softwood particles and fire-retardant chemicals mixed together at time of panel manufacture to achieve flame-spread index of 25 or less and smoke-developed index of 25 or less per ASTM E 84.

D. Fire-Retardant Fiberboard: Medium-density fiberboard panels complying with ANSI A208.2, made from softwood fibers, synthetic resins, and fire-retardant chemicals mixed together at time of panel manufacture to achieve flame-spread index of 25 or less and smoke-developed index of 200 or less per ASTM E 84.

2.3 CABINET HARDWARE AND ACCESSORIES

A. General: Provide cabinet hardware and accessory materials associated with architectural cabinets, except for items specified in Division 08 Section "Door Hardware (Scheduled by Describing Products)."

B. Frameless Concealed Hinges (European Type): BHMA A156.9, B01602, 170 degrees of opening.

C. Back-Mounted Pulls: BHMA A156.9, B02011.

D. Wire Pulls: Back mounted, solid metal stainless steel, 6-27/32 inches long by 9/16 inch square, as supplied by Doug Mockett & Company, Inc., DP105/3 Series square pulls.

E. Adjustable Shelf Standards and Supports: BHMA A156.9, B04102; with shelf brackets, B04112.

F. Shelf Rests: BHMA A156.9, B04013; metal.

G. Drawer Slides: BHMA A156.9, B05091.

1. Heavy Duty (Grade 1HD-100 and Grade 1HD-200): Side mounted; full-extension type; zinc-plated steel ball-bearing slides.

H. Door Locks: BHMA A156.11, E07121.

I. Drawer Locks: BHMA A156.11, E07041.

J. Grommets for Cable Passage through Countertops: 2-inch (51-mm) OD, black, molded-plastic grommets and matching plastic caps with slot for wire passage.

K. Exposed Hardware Finishes: For exposed hardware, provide finish that complies with BHMA A156.18 for BHMA finish number indicated.

1. Satin Stainless Steel: BHMA 630.

L. For concealed hardware, provide manufacturer's standard finish that complies with product class requirements in BHMA A156.9.

2.4 MISCELLANEOUS MATERIALS

A. Furring, Blocking, Shims, and Hanging Strips: Fire-retardant-treated softwood lumber, kiln dried to less than 15 percent moisture content.

B. Anchors: Select material, type, size, and finish required for each substrate for secure anchorage. Provide nonferrous-metal or hot-dip galvanized anchors and inserts on inside face of exterior walls and elsewhere as required for corrosion resistance. Provide toothed-steel or lead expansion sleeves for drilled-in-place anchors.

C. Adhesives, General: Adhesives shall not contain urea formaldehyde.

D. VOC Limits for Installation Adhesives: Installation adhesives shall comply with the following limits for VOC content when calculated according to 40 CFR 59, Subpart D (EPA Method 24):

1. Wood Glues: 30 g/L.
2. Multipurpose Construction Adhesives: 70 g/L.
3. Contact Adhesive: 250 g/L.

E. Adhesive for Bonding Plastic Laminate: Contact cement.

1. Adhesive for Bonding Edges: Hot-melt adhesive or adhesive specified above for faces.

2.5 FABRICATION, GENERAL

A. Interior Woodwork Grade: Unless otherwise indicated, provide Premium-grade interior woodwork complying with referenced quality standard.

B. Wood Moisture Content: Comply with requirements of referenced quality standard for wood moisture content in relation to ambient relative humidity during fabrication and in installation areas.

C. Fabricate woodwork to dimensions, profiles, and details indicated. Ease edges to radius indicated for the following:

1. Corners of Cabinets and Edges of Solid-Wood (Lumber) Members 3/4 Inch (19 mm) Thick or Less: 1/16 inch (1.5 mm).
2. Edges of Rails and Similar Members More Than 3/4 Inch (19 mm) Thick: 1/8 inch (3 mm).

3. Corners of Cabinets and Edges of Solid-Wood (Lumber) Members and Rails: 1/16 inch (1.5 mm).

D. Complete fabrication, including assembly, finishing, and hardware application, to maximum extent possible before shipment to Project site. Disassemble components only as necessary for shipment and installation. Where necessary for fitting at site, provide ample allowance for scribing, trimming, and fitting.

1. Notify Architect seven days in advance of the dates and times woodwork fabrication will be complete.
2. Trial fit assemblies at fabrication shop that cannot be shipped completely assembled. Install dowels, screws, bolted connectors, and other fastening devices that can be removed after trial fitting. Verify that various parts fit as intended and check measurements of assemblies against field measurements indicated on Shop Drawings before disassembling for shipment.

E. Shop-cut openings to maximum extent possible to receive hardware, appliances, plumbing fixtures, electrical work, and similar items. Locate openings accurately and use templates or roughing-in diagrams to produce accurately sized and shaped openings. Sand edges of cutouts to remove splinters and burrs.

1. Seal edges of openings in countertops with a coat of varnish.

2.6 INTERIOR STANDING AND RUNNING TRIM FOR TRANSPARENT FINISH

A. Grade: Premium.

B. Wood Species and Cut: White maple, plain sliced.

C. For trim items wider than available lumber, use veneered construction. Do not glue for width.

D. Backout or groove backs of flat trim members and kerf backs of other wide, flat members, except for members with ends exposed in finished work.

E. Assemble casings in plant except where limitations of access to place of installation require field assembly.

F. Assemble moldings in plant to maximum extent possible. Miter corners in plant and prepare for field assembly with bolted fittings designed to pull connections together.

2.7 BUILT-IN DISPLAY CASES

A. Grade: Premium.

B. Wood Species and Cut: White maple, plain sliced.

C. For trim items wider than available lumber, use veneered construction. Do not glue for width.

D. Backout or groove backs of flat trim members and kerf backs of other wide, flat members, except for members with ends exposed in finished work.

E. Assemble casings in plant except where limitations of access to place of installation require field assembly.

F. Assemble moldings in plant to maximum extent possible. Miter corners in plant and prepare for field assembly with bolted fittings designed to pull connections together.

G. Slatwall Panels on back of case:

1. Orientation of Panels: Horizontal.
2. Panel Size: 4 feet high by 8 feet long.
3. Panels may be cut to adjust either the height or the length.
4. Spacing between the center of one groove to the center of another groove: 4 inches.
5. Finish: Paint grade to be field-painted.

H. Slatwall Accessories:

1. Slatwall Premium Shelf Brackets;

a. Finish: Chrome.
b. Sizes: 6-inch and 10-inch.
c. Application: For glass shelves.

I. Heat-Treated Float Glass: ASTM C 1048; Type I; Quality-Q3; Class I (clear) unless otherwise indicated; of kind and condition indicated.

1. Fabrication Process: By horizontal (roller-hearth) process with roll-wave distortion parallel to bottom edge of glass as installed unless otherwise indicated.
2. For uncoated glass, comply with requirements for Condition A.
3. Locations: Shelving and door pieces.
4. Thickness: 3/8-inch shelves and door.

J. Sliding Door Hardware:

1. Track: C. R. Lawrence Co., chrome plated double sliding track for glass doors. Adjustable nylon insert for glass doors¼ to ½ inches (6 to 12 mm). Top and bottom track required.
2. Rollers: C.R. Lawrence Co., chrome plated roller for glass door that correspond to sliding track. Four (4) rollers required for each piece of glass, two (2) on top and two (2) on bottom.
3. Lock: C. R. Lawrence Co., chrome plated pick-proof sliding glass door lock. It is adjustable to overlaps from 1 to 3 inches (25.4 to 76.2 mm). Comes with two (2) keys.

2.8 PLASTIC-LAMINATE CABINETS

A. Grade: Premium.

B. AWI Type of Cabinet Construction: As indicated on the Drawings.

C. Laminate Cladding for Exposed Surfaces: High-pressure decorative laminate complying with the following requirements:

1. Horizontal Surfaces Other Than Tops: Grade HGS.
2. Vertical Surfaces: Grade HGS.
3. Edges: Grade HGS.

D. Materials for Semiexposed Surfaces:

1. Surfaces Other Than Drawer Bodies: High-pressure decorative laminate, Grade VGS.

a. Edges of Plastic-Laminate Shelves: PVC T-mold matching laminate in color, pattern, and finish.
b. For semiexposed backs of panels with exposed plastic-laminate surfaces, provide surface of high-pressure decorative laminate, Grade VGS.

2. Drawer Sides and Backs: Thermoset decorative panels.
3. Drawer Bottoms: Thermoset decorative panels.

E. Concealed Backs of Panels with Exposed Plastic Laminate Surfaces: High-pressure decorative laminate, Grade BKL.

F. Colors, Patterns, and Finishes: Provide materials and products that result in colors and textures of exposed laminate surfaces complying with the following requirements:

1. As indicated in the “Finish Legend” on the drawings, and as listed above.

G. Provide dust panels of 1/4-inch (6.4-mm) plywood or tempered hardboard above compartments and drawers, unless located directly under tops.

2.9 PLASTIC-LAMINATE COUNTERTOPS

A. Grade: Premium.

B. High-Pressure Decorative Laminate Grade: HGS.

C. Colors, Patterns, and Finishes: Provide materials and products that result in colors and textures of exposed laminate surfaces complying with the following requirements:

1. As indicated in the “Finish Legend” on the drawings, and as listed above.

D. Edge Treatment: Same as laminate cladding on horizontal surfaces.

E. Core Material: Medium-density fiberboard made with exterior glue.

F. Core Material at Sinks: Medium-density fiberboard made with exterior glue or exterior-grade plywood.

G. Backer Sheet: Provide plastic-laminate backer sheet, Grade BKL, on underside of countertop substrate.

H. Paper Backing: Provide paper backing on underside of countertop substrate.

2.10 SOLID-SURFACING-MATERIAL COUNTERTOPS

A. Grade: Premium.

B. Solid-Surfacing-Material Thickness: 3/4 inch (19 mm).

C. Colors, Patterns, and Finishes: Provide materials and products that result in colors of solid-surfacing material complying with the following requirements:

1. As indicated in the “Finish Legend” on the drawings, and as listed above.

D. Fabricate tops in one piece, unless otherwise indicated. Comply with solid-surfacing-material manufacturer's written recommendations for adhesives, sealers, fabrication, and finishing.

1. Fabricate tops with shop-applied edges of materials and configuration indicated.
2. Fabricate tops with loose backsplashes for field application.

E. Drill holes in countertops for plumbing fittings and soap dispensers in shop.

2.11 BUILT-IN BENCHES WITH SEAT CUSHIONS

A. Grade: Premium.

B. Wood Species and Cut: White maple, plain sliced.

C. For trim items wider than available lumber, use veneered construction. Do not glue for width.

D. Backout or groove backs of flat trim members and kerf backs of other wide, flat members, except for members with ends exposed in finished work.

E. Assemble casings in plant except where limitations of access to place of installation require field assembly.

F. Assemble moldings in plant to maximum extent possible. Miter corners in plant and prepare for field assembly with bolted fittings designed to pull connections together.

G. Facing Material and Cushion Material: Apply fabric fully covering visible surfaces of cushion; with material stretched straight, on the grain, tight, square, and free from puckers, ripples, wrinkles, sags, blisters, seams, or other visible distortions or foreign matter.

1. Square Corners: Tailor corners.
2. Radius and Other Nonsquare Corners: Attach material so there are no seams or gathering of material.
3.

H. Install two (2) velcro strips on the back of each cushion and two (2) corresponding Velcro strips on the bench surface.

2.12 CLOSET AND UTILITY SHELVING

A. Grade: Premium.

B. Shelf Material: 3/4-inch (19-mm) medium-density fiberboard with high-pressure decorative laminate HGS grade on all exposed surfaces.

C. Cleats: Steel support bracket.

2.13 MANUFACTURED PENCIL DRAWER

A. HermanMiller Pencil Drawer, or equal.

B. Tray Material: Plastic

C. Color: Black

D. Glides: Integral glides to attached to bottom of work/counter top

E. Size: Depth 16.25”, Width 21.13”, H: 1.88”

2.14 SHOP FINISHING

A. Grade: Provide finishes of same grades as items to be finished.

B. General: Finish architectural woodwork at fabrication shop as specified in this Section. Defer only final touchup, cleaning, and polishing until after installation.

C. Preparation for Finishing: Comply with referenced quality standard for sanding, filling countersunk fasteners, sealing concealed surfaces, and similar preparations for finishing architectural woodwork, as applicable to each unit of work.

D. Transparent Finish:

1. Grade: Premium.
2. WI Finish System 1d.: Polyurethane.
3. Staining: None required.
4. Open Finish for Open-Grain Woods: Do not apply filler to open-grain woods.
5. Sheen: Satin, 31-45 gloss units measured on 60-degree gloss meter per ASTM D 523.

PART 3 - EXECUTION

3.1 PREPARATION

A. Before installation, condition woodwork to average prevailing humidity conditions in installation areas.

B. Before installing architectural woodwork, examine shop-fabricated work for completion and complete work as required, including removal of packing and backpriming.

3.2 INSTALLATION

A. Grade: Install woodwork to comply with requirements for the same grade specified in Part 2 for fabrication of type of woodwork involved.

B. Assemble woodwork and complete fabrication at Project site to comply with requirements for fabrication in Part 2, to extent that it was not completed in the shop.

C. Install woodwork level, plumb, true, and straight. Shim as required with concealed shims. Install level and plumb (including tops) to a tolerance of 1/8 inch in 96 inches (3 mm in 2400 mm).

D. Scribe and cut woodwork to fit adjoining work, refinish cut surfaces, and repair damaged finish at cuts.

E. Fire-Retardant-Treated Wood: Handle, store, and install fire-retardant-treated wood to comply with chemical treatment manufacturer's written instructions, including those for adhesives used to install woodwork.

F. Anchor woodwork to anchors or blocking built in or directly attached to substrates. Secure with countersunk, concealed fasteners and blind nailing as required for complete installation. Use fine finishing nails or finishing screws for exposed fastening, countersunk and filled flush with woodwork and matching final finish if transparent finish is indicated.

G. Standing and Running Trim: Install with minimum number of joints possible, using full-length pieces (from maximum length of lumber available) to greatest extent possible. Do not use pieces less than 36 inches (900 mm) long, except where shorter single-length pieces are necessary. Scarf running joints and stagger in adjacent and related members.

1. Fill gaps, if any, between top of base and wall with plastic wood filler, sand smooth, and finish same as wood base if finished.
2. Install standing and running trim with no more variation from a straight line than 1/8 inch in 96 inches (3 mm in 2400 mm).

H. Cabinets: Install without distortion so doors and drawers fit openings properly and are accurately aligned. Adjust hardware to center doors and drawers in openings and to provide unencumbered operation. Complete installation of hardware and accessory items as indicated.

1. Install cabinets with no more than 1/8 inch in 96-inch (3 mm in 2400-mm) sag, bow, or other variation from a straight line.
2. Maintain veneer sequence matching of cabinets with transparent finish.
3. Fasten wall cabinets through back, near top and bottom, at ends and not more than 16 inches (400 mm) o.c.

I. Countertops: Anchor securely by screwing through corner blocks of base cabinets or other supports into underside of countertop.

1. Align adjacent solid-surfacing-material countertops and form seams to comply with manufacturer's written recommendations using adhesive in color to match countertop. Carefully dress joints smooth, remove surface scratches, and clean entire surface.
2. Install countertops with no more than 1/8 inch in 96-inch (3 mm in 2400-mm) sag, bow, or other variation from a straight line.
3. Secure backsplashes to walls with adhesive.
4. Calk space between backsplash and wall with sealant specified in Division 07 Section "Joint Sealants."

J. Touch up finishing work specified in this Section after installation of woodwork. Fill nail holes with matching filler where exposed.

3.3 ADJUSTING AND CLEANING

A. Repair damaged and defective woodwork, where possible, to eliminate functional and visual defects; where not possible to repair, replace woodwork. Adjust joinery for uniform appearance.

B. Clean, lubricate, and adjust hardware.

C. Clean woodwork on exposed and semiexposed surfaces. Touch up shop-applied finishes to restore damaged or soiled areas.

END OF SECTION 064023